


EXISTING PLAN - SHOWN FOR REFERENCE ONLY

ENLARGED PATIO PLAN

SCOPE OF WORK

REMAINDER OF EXISTING

PATIO NOT, IN SCOPE



NINFAS CONSTRUCTION SPECIFICATIONS.docx. 7

DIVISION 16 **ELECTRICAL**

16100 ELECTRICAL REQUIREMENTS

site prior to bid or estimate.

NOTE: Relocate and/or provide new tenant standard electrical outlets in order to suit new construction. Provide new cover plates for existing outlets as necessary. Provide blank outlet cover plates as necessary. All outlets and switches shall be the same color. Mounting height for new/relocated electrical outlets to be 15" A.F.F. to the bottom of outlet cover plates unless noted otherwise. Electrical/ telephone/data outlet combinations to be mounted other side of the same stud. Stagger outlets from one side to the other of walls to inhibit transfer of sound. Existing

otherwise. Outlet Color: Brushed Aluminum

16500 LIGHTING FIXTURES

REFER TO ELECTRICAL LIGHTING PLAN(S) IN CONSTRUCTION DOCUMENT SET

NOTE: Lighting fixture alternates and substitutions shall <u>not</u> be used unless written approval by designer is obtained by General Contractor.

NOTE: All lamps used in this project shall comply with the most current lighting regulations and codes as required by local and governing authorities.

NOTE: Provide 4 submittal cut sheets of all new lighting fixtures for Interior Designer approval prior to ordering and installation of lighting fixtures. Submittals that are not both received and approved by Interior Designer shall be understood to be "not approved" by Interior Designer.

NOTE: Relocate and/or provide new tenant standard switches in order to suit new construction. Provide new cover plates for existing switches as necessary. All outlets and switches shall be the same color. Mounting height for new/relocated switches to be 48" A.F.F. to top of switch cover plates unless noted otherwise. Existing

switches to remain unless otherwise Switch Color: Brushed Aluminum

16700 TELEPHONE REQUIREMENTS

NOTE: General Contractor shall

provide conduit and J-Box or mud ring

REFER TO ELECTRICAL POWER PLAN(S) IN CONSTRUCTION DOCUMENT SET

NOTE: Electrical subcontractor to visit

and string for all telephone outlets. Verify existing tenant or building standard and match. NOTE: Combine telephone and data if outlets are shown as combined. NOTE: Mounting height for new/relocated telephone outlets to be 15" A.F.F. to the bottom of outlet cover plates unless noted otherwise. Electrical/telephone/data outlet combinations to be mounted other side of the same stud. Stagger outlets from one side to the other of walls to inhibit transfer of sound.

outlets to remain unless noted NOTE: All cable (transmission wire) provided and installed by Tenant as

> Tenant to provide feeder cable from the building telephone/electric room (closest location on floor to suite) to telephone switch gear within suite.

> Tenant to provide cable from telephone switch to all telephone outlets as shown on plan.

> Tenant to provide telephone switch equipment as per their needs and

> requirements. Tenant to provide new cover plates for existing telephone outlets as

necessary. Tenant to provide telephone outlets as

Tenant to provide new telephone outlets for wall phones as shown. Mounting height for wall telephone

outlets to be 48" A.F.F. to the top of

outlet cover plates unless noted otherwise. Tenent to provide dedicated phone outlet for fax as shown.

16800 DATA REQUIREMENTS

Tenant to provide flush floor telephone outlets as shown.

REFER TO ELECTRICAL POWER PLAN(S) IN CONSTRUCTION DOCUMENT SET

NOTE: General Contractor shall provide conduit and J-Box or mud ring and string for all data outlets. Verify existing tenant or building standard

NOTE: Combine telephone and data if outlets are shown as combined.

NOTE: Mounting height for new/relocated data outlets to be 15" A.F.F. to the bottom of outlet cover plates unless noted otherwise. Electrical/telephone/data outlet combinations to be mounted other side of the same stud. Stagger outlets from one side to the other of walls to inhibit transfer of sound.

NOTE: General Contractor shall provide J-Boxes (separate from electrical) to feed data for systems furniture as shown. Combine telephone and data if outlets are

NOTE: All cable (transmission wire) provided and installed by Tenant as

shown as combined.

Tenant to provide cable from telephone switch or patch panel to all data outlets as shown on plan.

Tenant to provide all equipment and connection/patch equipment as per their needs and requirements.

Tenant to provide new cover plates for

existing data outlets as necessary.

Tenant to provide data outlets as

NOTE: Tenant to provide flush floor data outlets as shown.

CONDITIONS.

GENERAL CONTRACTOR SHALL VISIT THE SITE/SUITE IN ORDER TO CONFIRM UNIT QUANTITIES OF BUILDING MATERIALS AND/OR OTHER EXISTING CONDITIONS WHICH MAY HAVE AN IMPACT ON COST. ALL DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THIS OFFICE. RECEIPT OF BID INDICATES THAT THE GENERAL CONTRACTOR IS IN CONFORMANCE WITH THE INTENT OF THESE DRAWINGS AND AS BUILT

bar napkin producti 2944 n 44th street • s phoenix, az 85018 602 • 492 • 9494 www.bnp-llc.com



THE

2704 NAVIG HOUSTOI

CITY SUBM