



A. FLOOR PLAN  
SCALE: 1/4" = 1'-0"  
AREA: 3,000 SQ.FT.

FLOOR PLAN KEY NOTES

- 1 CO2 TANK PROVIDED BY OWNER
- 2 LINE OF EXHAUST HOOD ABOVE - SEE MECHANICAL DRAWINGS
- 3 ELECTRICAL PANELS - ELECTRICAL DRAWINGS
- 4 WATER HEATER MOUNTED ABOVE MOP SINK - SEE PLUMBING DRAWINGS
- 5 G.C. SHALL COORDINATE INSTALLATION OF CORNER CLOSURE ANGLES @ WALK-IN COOLER/FREEZER W/ EQUIPMENT SUPPLIER.
- 6 LINE OF GYP. SOFFIT OR BULKHEAD ABOVE. REFER TO REFLECTED CEILING PLAN.
- 7 SODA LINES TO RUN OVERHEAD & DOWN IN WALL TO DISPENSERS.
- 8 ELECTRIC HAND DRIER
- 9 EXPOSED STL. COLUMN - PAINTED P-1 SEAL JUNCTION OF COLUMN & FFP FINISH W/ WHITE, MILDEW RESISTANT SILICONE.
- 10 DRIVE THRU WINDOW - CAULK ALL PERIMETER EDGES
- 11 PROVIDE BLOCKING FOR SUPPORT OF SHELVING @ KITCHEN WALLS. BLKG MAY BE 5/8" PLYWOOD IN LEW OF GYP. BD.
- 12 TRANSITION WALL FINISHES AT CORNER. REFER ALSO TO INTERIOR ELEVATIONS.
- 13 ABOVE SOFFIT LINE.

KEY TO WALL TYPES:

FULL HEIGHT WALLS: 20 GA. STEEL STUDS @ 16" O.C. EXTEND 6" ABOVE HIGHEST ADJACENT CEILING & BRACE TO STRUCTURE ABOVE PER DETAIL 4 & 5 AND/OR AS SHOWN. SEE PLAN FOR REOD DEPTH. INSTALLATION. SEE PLAN FOR REOD DEPTH.

MILLWORK SCHEDULE

ITEM NO	QTY	EQUIPMENT CATEGORY	REMARK
A	1	PICK-UP COUNTER	REFER RO MILLWORK GENERAL NOTES
B	1	BEVERAGE COUNTER	REFER RO MILLWORK GENERAL NOTES
C	1	DRIVE-THRU BEVERAGE COUNTER	REFER RO MILLWORK GENERAL NOTES
D	2	OPERING COUNTER	REFER RO MILLWORK GENERAL NOTES
E	2	OPERING COUNTER	REFER RO MILLWORK GENERAL NOTES
F	1	MERCHANDISE DISPLAY	REFER RO MILLWORK GENERAL NOTES
G	1	CHIP SHELVEING	REFER RO MILLWORK GENERAL NOTES
H1	1	TRASH UNIT	REFER RO MILLWORK GENERAL NOTES
H2	1	TRASH UNIT	REFER RO MILLWORK GENERAL NOTES
J	1	OFFICE DESK	REFER RO MILLWORK GENERAL NOTES
K	1	LIGHTING DRUM	REFER RO MILLWORK GENERAL NOTES
L	1	VANITY	REFER RO MILLWORK GENERAL NOTES

MILLWORK GENERAL NOTES:

1. M.V. IS THE ABBREVIATION FOR MILLWORK VENDOR AND SHALL BE ANY OF THE APPROVED SCHLOTZSKY'S VENDORS AS VERIFIED BY OWNER. MIDWEST CABINET KANSAS 6006; CONNOR INDUSTRIES BRESSLER OTTAWA, (785)242-8181 OR EBESSETTE@MIDWESTCABINET.COM WITH QUESTIONS RELATION TO THE MILLWORK PACKAGE.
2. A COMPLETE SET OF MILLWORK SHOP DRAWINGS SHALL BE FURNISHED BY THE VENDOR TO THE ARCHITECT FOR USE AND REFERENCE PERTAINING TO THE CONSTRUCTION OF THE PROJECT. THESE SHOP DRAWINGS SHALL BE CONSIDERED AS AN INTEGRAL PART OF THE CONTRACT DOCUMENTS FOR THE CONSTRUCTION OF THE PROJECT.
3. ALL ITEMS LISTED IN THE MILLWORK SCHEDULE SHALL BE FURNISHED BY THE OWNER (MILLWORK VENDOR) AND SHALL BE INSTALLED BY THE G.C. IN ADDITION TO THE ITEMS SPECIFICALLY NOTED IN THE MILLWORK SCHEDULE. ALL STANDING AND FINISHING TIM SHALL ALSO BE FURNISHED BY THE MILLWORK VENDOR AND SHALL BE INSTALLED BY THE G.C.
4. ALL MILLWORK ITEMS, INCLUDING STANDING AND RUNNING TRIM, CASINGS, DOORS, ETC., SHALL BE FURNISHED TO THE JOB SITE IN PREPARED CONDITION (I.E. STAINED, SEaled, MANAGED, ETC.) UNLESS SPECIFICALLY NOTED OTHERWISE.
5. THE MILLWORK VENDOR SHALL FURNISH TOUCH-UP STAIN, COLORED PUTTY AND VARNISH AS PART OF THE MILLWORK PACKAGE. MILLWORK SHALL BE STAINED BY G.C. TO TOUCH UP JOLES, CUTS, AND WARRD AREAS DURING AND/OR AFTER INSTALLATION. ALL END CUTS, MITERS, RIP CUTS, ECT., SHALL BE STAINED AND SEALED TO ENSURE THAT NO UNFINISHED WOOD EDGES ARE EXPOSED TO VIEW OR WILL BE EXPOSED TO VIEW IN THE PRODUCT.

Rev.	By	Date

**SCHLOTZSKY'S**  
**@ VICTORY LAKETOWN CENTER**  
**TRACT 7A NEC INTERSTATE HWY 45 & F.M.646**  
**LEAGUE CITY, TEXAS 77573**

**ARCH**  
Woo Associates, LLC.  
ARCHITECTS - PLANNERS  
13734 Branford Green Dr.  
Houston, TX 77083  
(281) 530-3192

Date	05-26-2010
Scale	AS SHOWN
Drawn by	KW
Job#:	VICTORY LAKE

**A2.0**