



A. FLOOR PLAN
SCALE - 1/4" = 1'-0"
AREA: 3,000 SQ.FT.

FLOOR PLAN KEY NOTES

- 1 CO2 TANK PROVIDED BY OWNER
- 2 LINE OF EXHAUST HOOD ABOVE - SEE MECHANICAL DRAWINGS
- 3 ELECTRICAL PANELS - ELECTRICAL DRAWINGS
- 4 WATER HEATER MOUNTED ABOVE MOP SINK - SEE PLUMBING DRAWINGS
- 5 G.C. SHALL COORDINATE INSTALLATION OF CORNER CLOSURE SUPPLIER @ WALK-IN COOLER/FREEZER W/ EQUIPMENT SUPPLIER.
- 6 LINE OF GYP. SOFFIT OR BULKHEAD ABOVE. REFER TO REFLECTED CEILING PLAN.
- 7 SODA LINES TO RUN OVERHEAD & DOWN IN WALL TO DISPENSERS.
- 8 ELECTRIC HAND DRIER
- 9 EXPOSED STL. COLUMN - PAINTED P-1 SEAL JUNCTION OF COLUMN & FRP FINISH W/ WHITE, MILDEW RESISTANT SILICONE.
- 10 DRIVE THRU WINDOW - CAULK ALL PERIMETER EDGES
- 11 PROVIDE BLOCKING FOR SUPPORT OF SHELVING @ KITCHEN WALLS. BLKG MAY BE 5/8" PLYWOOD IN LEW OF GYP. BD.
- 12 TRANSITION WALL FINISHES AT CORNER. REFER ALSO TO INTERIOR ELEVATIONS.
- 13 ABOVE SOFFIT LINE.
- 14 HOT & COLD WATER FOR COFFEE MACHINE

KEY TO WALL TYPES.

FULL HEIGHT WALLS: 20 GA. 3 5/8" STEEL STUDS (6" STUDS @ PLUMBING WALL) @ 16" O.C. EXTEND 6" ABOVE HIGHEST ADJACENT CEILING & BRACE TO STRUCTURE ABOVE PER DITS 4 & 5/44.0 OR AS OTHERWISE NOTED TO ACHIEVE A SOUND, STABLE INSTALLATION. SEE PLAN FOR REOD DEPTH.

MILLWORK SCHEDULE

ITEM NO	QTY/EQUIPMENT CATEGORY	REMARK
A	1 PICK-UP COUNTER	REFER RO MILLWORK GENERAL NOTES
B	1 BEVERAGE COUNTER	REFER RO MILLWORK GENERAL NOTES
C	1 DRIVE-THRU BEVERAGE COUNTER	REFER RO MILLWORK GENERAL NOTES
D	2 ORDERING COUNTER	REFER RO MILLWORK GENERAL NOTES
E	2 ORDERING COUNTER	REFER RO MILLWORK GENERAL NOTES
F	1 MERCHANDISE DISPLAY	REFER RO MILLWORK GENERAL NOTES
G	1 CHIP SHELVING	REFER RO MILLWORK GENERAL NOTES
H1	1 TRASH UNIT	REFER RO MILLWORK GENERAL NOTES
H2	1 TRASH UNIT	REFER RO MILLWORK GENERAL NOTES
J	1 OFFICE DESK	REFER RO MILLWORK GENERAL NOTES
K	1 LIGHTING BULK	REFER RO MILLWORK GENERAL NOTES
L	1 VANITY	REFER RO MILLWORK GENERAL NOTES

MILLWORK GENERAL NOTES.

1. M.V. IS THE ABBREVIATION FOR MILLWORK VENDOR AND SHALL BE ANY OF THE APPROVED SCHLOTZSKY'S VENDORS AS LISTED IN THE MILLWORK GENERAL NOTES. CONTACT ED BESSETTE (785)242-8181 OR EBESSETTE@MIDWESTCABINET.COM WITH QUESTIONS RELATION TO THE MILLWORK PACKAGE.
2. A COMPLETED SET OF MILLWORK SHOP DRAWINGS SHALL BE FURNISHED TO THE OWNER. THE MILLWORK GENERAL NOTES, USE AND REFERENCE PERTAINING TO THE CONSTRUCTION OF THE PROJECT. THESE SHOP DRAWINGS SHALL BE CONSIDERED AS AN INTEGRAL PART OF THE CONTRACT DOCUMENTS FOR THE CONSTRUCTION OF THE PROJECT.
3. ALL ITEMS LISTED IN THE MILLWORK SCHEDULE SHALL BE FURNISHED BY THE OWNER (MILLWORK VENDOR) AND SHALL BE SPECIFICALLY NOTED IN THE MILLWORK SCHEDULE. ALL STANDING AND RUNNING TRIM SHALL ALSO BE FURNISHED BY THE OWNER (MILLWORK VENDOR) AND SHALL BE INSTALLED BY THE G.C.
4. ALL MILLWORK ITEMS, INCLUDING STANDING AND RUNNING TRIM, CASINGS, DOORS, ETC., SHALL BE FURNISHED TO THE JOB SITE IN PREFINISHED CONDITION (I.E. STAINED, SEALED, LAMINATED, ETC.) UNLESS SPECIFICALLY NOTED OTHERWISE.
5. THE MILLWORK VENDOR SHALL FURNISH TOUCH-UP STAIN, COLORED PUTTY AND VARNISH AS PART OF THE MILLWORK PACKAGE. THESE ITEMS SHALL BE USED BY THE G.C. TO TOUCH UP JOLES, CUTS, AND VARRED AREAS DURING AND/OR AFTER INSTALLATION. ALL END CUTS, JOLES, CUTS, AND VARRED AREAS SHALL BE REPAIRED TO ENSURE THAT UNFINISHED WOOD EDGES ARE SEALED EXPOSED TO VIEW OR WILL BE EXPOSED TO VIEW IN THE PRODUCT.

Rev	By	Date

SCHLOTZSKY'S
@ VICTORY LAKETOWN CENTER
TRACT 7A NEC INTERSTATE HWY 45 & F.M.646
LEAGUE CITY, TEXAS 77573

ARCH
WOO Associates, LLC.
ARCHITECTS - PLANNERS
13734 Bramford Green Dr.
Houston, TX 77085
(281) 530-3192

Date	09-09-2010
Scale	AS SHOWN
Drawn by	KW
Job#	VICTORY LAKE
A2.0	